









SOIL REINFORCEMENT

Case Study

application

GRS-IBS

location product Sunfield, MI - Keefer Road over Sebewa Creek

Mirafi® HP570

job owner

engineer date of installation

FHWA / MDOT/ Ionia County **Road Comm** Milbocker & Sons, Inc. September 2014

TenCate develops and produces materials that function to increase performance, reduce costs and deliver measurable results by working with our customers to provide advanced solutions.

THE CHALLENGE

In Sunfield, MI, Ionia Couny needed to disassemble the existing deteriorated bridge over Sebewa Creek and replace it with as little highway down time as possible. In addition, due to budget constraints, the bridge reconstruction had to be very cost effective.

THE DESIGN

To meet the limited budget for building the abutments, the Federal Highway Administration (FHWA) Geosynthetic Reinforced Soil Integrated Bridge System (GRS-IBS) was chosen. This system is the core of FHWA's initiative for innovative bridge construction for this type of abutment. It is derived from examples of ancient structures that utilize closely spaced reinforcement members, usually some type of organic material, to reinforce soil. The principles are the same for this modern design adaptation by using angular, crushed gravel with a high strength geotextile or geogrid in frequent layers. The interactions of these components stabilize the structure internally. TenCate Mirafi® HP570 geotextiles were chosen for this project. Although there are now over 100 GRS-IBS bridges in service throughout the country, the Ionia County GRS-IBS bridge is the first in the state of Michigan. The construction technique did not require deep foundation design and thus could be completed in much less time, usually just weeks. It also utilizes basic earthwork methods and practice with minimal environmental impact.



The cut Mirafi® HP570 placed behind the block



Block facade is placed as geotextile reinforcement and stone lifts are brought up.







THE CONSTRUCTION

TenCate Mirafi® geosynthetics fit perfectly into the design for two of the components of this bridge system. The Reinforced Soil Foundation was constructed using Mirafi® HP570 to achieve the needed confinement and reinforcement for the base support of this structure. It consists of select gravel compacted and encapsulated in the Mirafi® HP570 geotextile fabric to function as an integral base for the abutment. Next, the abutment was built by placing alternating layers of select gravel and geosynthetic reinforcement in 12" lifts. The final course of block was capped with ready-mix concrete.

The ease of construction using the flexible TenCate materials along with the simple installation techniques increased worker safety and decreased the time to complete the project.

THE PERFORMANCE

The bridge is now in service and the performance is outstanding. Monitoring has been in place since the beginning of construction with no issues. In addition to saving the county significant construction costs, there has been no maintenance cost.



Stone is placed behind the block, on top of Mirafi® HP570. Care must be taken with loading until compaction is adequate.



Completed Keefer Highway Bridge abutment ready for traffic.

TenCate Geosynthetics Americas assumes no liability for the accuracy or completeness of this information or for the ultimate use by the purchaser. TenCate Geosynthetics Americas disclaims any and all express, implied, or statutory standards, warranties or guarantees, including without limitation any implied warranty as to merchantability or fitness for a particular purpose or arising from a course of dealing or usage of trade as to any equipment, materials, or information furnished herewith. This document should not be construed as engineering advice.

Mirafi® is a registered trademark of Nicolon Corporation.

© 2015 TenCate Geosynthetics Americas







